

MYSORE DIVISION.

Dated 19th February 1912.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 12th March 1912, for restoring the Melur breached tank, R. No.—Hunsur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1914.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Mysore, between the hours of 11 A.M. and 5 P.M., on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one thousand in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring the Melur breached tank, R. No.—Hunsur Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Detailed abstract of restoring the Melur breached tank R. No.—of Hunsur Taluk.

Items of work	Per	Quantity
Bund R. L. 60'00—		
Earthwork, including watering and tamping	C. yd.	60,365
Turfing the slopes	Sqr.	1487.97
Grade stones with bed slabs	Each	34
Vis-a-vis stones	"	34
Registered No. stones	"	1
Date stones	"	1
Gauge stone in masonry structure	"	1
Clearing jungle	Lump sum	Rs.
Cutting bund to receive new earth	Lump sum	"
Bailing water	"	"
New stone work	C. yd.	65.13
Earthwork (excavation for foundation of puddle, etc.)	"	48.54
Puddle wall of fine gravel and brick work	"	957.
Clearing slip in breaches	Lump sum	Rs.
Gravelling to the revetment— $\frac{1}{4}$ mile lead	C. yd.	1,085
Sluice No. 1, R. L. 40'00—		
Brick in surki mortar	C. ft.	1,367
Burnt stone slabs	S. ft.	370
Plastering with surki mortar	Sqr.	3,637
Rough stone with surki mortar	C. ft.	969
Pointing with surki mortar	Sqr.	2,80
Rough stone flooring	C. yd.	8
Earthwork (excavation, etc.)	"	250
Boring holes in slabs and wooden plug, etc.	Lump sum	Rs.

Sluice No. 2, R. L. 40'00—

Details as per No. 1 Sluice.

<i>Items of work</i>	<i>Per</i>	<i>Quantity</i>
Left waste weir, 115 feet long at R. L. 53'00—		
Earthwork	C. yd.	149
Concrete filling	C. ft.	154
Brick in surki mortar	„	1,361
Burnt stone slabs neatly dressed	S. ft.	208
Plastering with surki mortar	Sqr.	1'15
New rough stone work	C. yd.	86
Pin and cross burnt stone slabs	S. ft.	228
Clearing draft in front and rear	Lump sum	Rs.
Right waste weir, 200 feet long at R. L. 53'00—		
Earthwork (excavating foundations)	C. yd.	135
Brick in surki mortar	C. ft.	1,149
Burnt stone slabs neatly dressed	S. ft.	337
Plastering with surki mortar	Sqr.	4'40
New rough stone work	C. yd.	158
Clearing draft in front and rear	Lump sum	Rs.
Distribution—		
Constructing an aqueduct	Lump sum	Rs.

R. V. SUNDARAM IYER,
Executive Engineer.

KADUR DIVISION.

Dated 22nd February 1912.

The attention of the public is invited to the notification published in the *Mysore Gazette* dated 29th February 1912, calling for tenders for constructing a Male Lock-up building in the compound of the existing Jail at Chikmagalur, Kadur District.

R. S. NAVARATNA,
Executive Engineer.

CHITALDRUG DIVISION.

Abstract Notification.

It is hereby notified that sealed tenders for "Constructing Combined Bonded Warehouse and Sub-Registrar's Office at Chitaldrug" will be received by the Executive Engineer, Chitaldrug Division, up to the 19th March 1912.

For particulars, please see page 342 of the *Mysore Gazette* dated 29th February 1912.

Abstract Notification.

It is hereby notified that sealed tenders for "Constructing Combined Bonded Warehouse and Sub-Registrar's Office at Davangere" will be received by the Executive Engineer, Chitaldrug Division, up to 19th March 1912.

For particulars, please see page 341 of the *Mysore Gazette* dated 29th February 1912.

C. KRISHNA LYENGAR,
Executive Engineer.